

		SAFE WORK METHOD STATEMENT (SWMS) PART 1						
ACTIVITY: SAFETY HA	RNESS		sv	VMS #:				
BUSINESS NAME: Coast	tal Hire And Sales Pty L	td	AE	SN: 70114481408				
Business Address: 33	Jindalee rd, Port Macq	uarie, NSW 24	144					
BUSINESS CONTACT:			Рн	one #: 0429810200				
	SI	WMS Appro	VED BY: EMPLOYER / PCBU / DIRECTOR / OWN	IER.				
NAME:								
SIGNATURE:			DA	TE:				
PERSON/S RESPONSIBLE	ERSON/S RESPONSIBLE FOR ENSURING COMPLIANCE WITH SWMS:							
PERSON/S RESPONSIBLE	For reviewing the SWI	MS:						
RELEVANT WORKERS CONSULTED IN THE DEVELOPMENT, APPROVAL AND COMMUNICATION OF THIS SWMS.			ALL PERSONS INVOLVED IN THE TASK MUST HAVE THIS SWMS COMMUNICATED TO THEM BEFORE WORK COMMENCES.					
NAME	SIGNATURE	DATE	Tool Box Talks will be undertaken to identify, contro	l and communicate additional site hazards.				
			Work must cease immediately if incident or near mis consultation with relevant persons.	s occurs. SWMS must be amended in				
			Amendments must be approved by before work resumes.	and communicated to all affected workers				
			SWMS must be made available for inspection or rev	iew as required by WHS legislation.				
			Record of SWMS must be kept as required by WHS involved in a notifiable incident).	legislation (until job is complete or for 2 years if				
	PRINCIPA	L CONTRACT	OR DETAILS (The builder or the organisation you are	working for.)				
PRINCIPAL CONTRACTOR	R (PC):		PROJECT NAME:	DATE SWMS PROVIDED TO PC:				
Project Address:								
PROJECT MANAGER (PM	1):		PM SIGNATURE:	CONTACT PH. #:				
SWMS SCOPE: (TO BE I	FILLED IN ACCORDING TO C	N-SITE SPECIF	ics)					



	This work activity involves the following "High Risk Construction Work"												
☐ Confined	Spaces		☐ Mobile F	Plant		[□ Demolition □ Asbestos						
☐ Using ex	plosives		☐ Diving w	ork		[☐ Artificial extremes of temperature ☐ Tilt up or pre-cast concrete						
☐ Pressurised gas distribution mains or piping chemical, fuel or refrigerant lines energised electrical installations or services													
	☐ Structures or buildings involving structural alterations or repairs that require temporary support to prevent collapse												
	nvolves a risk	of a person fa	alling more th	an 2m, ir	ncluding work o	on tele	ecommu	inications towers					
□ Working	at depths grea	ater than 1.5 I	Metres, includ	ding tunne	els or mines		□ Wor	k in an area that r	nay have a	contaminated or fla	ımmable atr	nosphe	re
□ Work car	ried out adjac	ent to a road,	railway or sh	nipping la	ne, traffic corrid	dor	☐ In or	near water or oth	ner liquid tha	at involves risk of d	rowning		
LIKELIHOOD	Insignificant	MINOR	MODERATE	Major	CATASTROPHIC	Sc	CORE	Action	н	IERARCHY OF CO	NTROLS		Most Effectiv E
ALMOST CERTAIN	3 Нідн	3 High	4 Acute	4 Acute	4 А сите					ELIMINATIO	N		1
LIKELY	2 Moderate	3 Нідн	3 Ні G н	4 Acute	4 Acute	_	4A CUTE	DO NOT PROCEED.		Substitution	ON		
Possible	1 Low	2 Moderate	3 Нідн	4 ACUTE	4 Acute		3Н Нібн	Review before commencing work.		ISOLATION ENGINEE			
UNLIKELY	1 Low	1 Low	2 Moderate	3 Нідн	4 Acute		2M DERATE	Maintain control measures.		RAYS- MIN			•
RARE	1 Low	1 Low	2 Moderate	3 Нідн	3 High		1L Low	Record and monitor.		P			LEAST EFFECTIV E
Pi	ERSONAL PR	OTECTIVE E	QUIPMENT (PPE): <i>E</i>	NSURE ALL PPE	MEE	TS RELE	VANT AUSTRALIAN	STANDARDS.	INSPECT, AND REPL	ACE PPE AS	NEEDEL).
FOOT PROTECTION	HEARING PROTECTION	HIGH VISIBILITY	HEAD PROTECTION	EY PROTE			HAN PROTEC		BREATHII PROTECTI		FALL ARREST	jewelle	s, watches, ery that may se entangled
		(X)	(EY							30'		not be and loc	chines must worn. Long se hair must ied back.
AS 1319-1994	☐ 4 SAFETY SIGNS FO	DR THE OCCUPATION	☐ ONAL ENVIRONME	NT REPRODU	JCED WITH PERMISS	SION FR	□ ROM SAI G	LOBAL UNDER LICENCE	П 1210-с062. Sт	ANDARDS MAY BE PURCH	☐ ASED AT <u>HTTP://</u>	/WWW.SAI	GLOBAL.COM



Јов Ѕтер	POTENTIAL HAZARD/S	IR	CONTROL MEASURES TO REDUCE RISK	RR	RESPONSIBLE PERSON
JOB STEP 1. Planning & preparation	Lack of consultation may lead to potential outcomes for personal injury, property damage &/or environmental incident.	IR	Inherent Risk-rating (IR) Liaise with Principal Contractor to establish the following on-site systems and procedures are in place and take note of: Health and Safety rules Induction for all workers — site specific and toolbox meetings Supervisory arrangements Emergency plans All relevant workers are appraised for required competencies & for any pre-existing medical conditions if working in remote or isolated locations. Communication arrangements Hazard reporting procedures Injury reporting procedures Ensure Work Safe notification for deep excavations prior for planned work (where applicable) PPE required Site plans — showing no go zones for pedestrians Traffic Management Plan detailing movement of vehicles during work Exclusion Zones Risk Assessments, SWMS and JSA's Ensure relevant guidance material for electrical NO GO ZONES is on site and consulted before work commences.	RR	
			 and consulted before work commences. Underground essential services - including gas, water, sewerage, telecommunications, and electricity. 		



JOB STEP	POTENTIAL HAZARD/S	IR	CONTROL MEASURES TO REDUCE RISK	RR	RESPONSIBLE PERSON
2. Training and Capabilities	Lack of training or the assessment of capability may lead to personal injury, property damage &/or environmental incident.		Inherent Risk-Rating (IR) Ensure all persons entering site have a General Construction Induction Card (white card). Check that plant operators are appropriately qualified with correct licence endorsements for the applicable item of plant. Ensure all relevant workers have undertaken training and/or received instruction in the use of control measures. Include: Instructed on the use of this SWMS Reporting procedures for incidents Correct use of equipment including selecting, fitting, use, care of and maintenance Correct use of all tools used Emergency plans Use of supervision where required (e.g. new starters or new equipment) Conduct a pre-start toolbox talk to ensure that all workers have been made fully aware of the scope of work to be performed NOTE: Check workers are in fit condition to work i.e. no signs of fatigue, alcohol or drugs.		
	Powered mobile plant		IMPORTANT: If operating powered mobile plant e.g. excavator, skid steer etc., for this task, ensure there are separate, dedicated SWMS for the plant and that all workers/employees have relevant training and licensing		
3. Assess onsite conditions	Lack of a clear assessment may lead to personal injury, property damage &/or environmental incident.		 Assess conditions at site on arrival. Ensure: Ensure site-specific induction is undertaken (include location of amenities, first aid facilities, emergency plans and evacuation points, incident reporting, communication, contact persons etc.) Assess mobile phone reception (alternative emergency communications procedures in place if no reception available) Work site is exactly as detailed in Terms of Agreement or contract Suitable access for all equipment required 		



Ј ОВ Ѕ ТЕР	POTENTIAL HAZARD/S	IR	CONTROL MEASURES TO REDUCE RISK	RR	RESPONSIBLE PERSON
			INHERENT RISK-RATING (IR) RESIDUAL RISK-RATING (RR) - Suitable space for operation of equipment		
			Suitable space for operation of equipment Suitable lighting, including night-works (include flood lighting and operator head lamps as applicable)		
			 Consult with the person you are carrying out the work for on the potential hazards and risks associated with the task 		
			 If represented by an elected health and safety representative, the representative should be included in any consultation 		
			 Any other persons on site who are affected by the same matter are consulted and co-operative arrangements are made 		
			Conduct risk assessment to identify potential hazards e.g.		
			- Changes in levels		
			- Underground/overhead electrical services		
			- Mobile plant		
			- Hot conditions.		
4. Set up work area	Contact with electricity		Ensure work is not conducted in close proximity to electrical power lines. Check for:		
			 Overhead power lines (including high and low voltage distribution conductors) 		
			- Single wire earth return (SWER)		
			- Service cables to premises		
			- Communications cables		
			- Electrical transformers (mounted lower than cables)		
			Identify maximum range of equipment and how close equipment or load can come to asset (known as design envelope) the following dimensions are taken from the closest point of any extended component of the machine e.g. extended long reach boom		
			In general, for up to and including 132,000 volts		



JOB STEP	POTENTIAL HAZARD/S	IR	CONTROL MEASURES TO REDUCE RISK	RR	RESPONSIBLE PERSON
			INHERENT RISK-RATING (IR) RESIDUAL RISK-RATING (RR) - 3m above, either side and below power lines is No Go Zone.		
			· ·		
			- Between 3-6.4m of power lines a Spotter is required.		
			- Further than 6.4m of power lines is open area		
			- No work to be conducted within 10m radius of SWER transformer.		
			NOTE: No work to be conducted within Minimum Clearance Zones without written permission from power supplier.		
			IMPORTANT: Approach distances will vary based on the voltage level of the live electrical apparatus. Always contact your local power asset owner for information prior to commencing crane operations if unsure.		
	Underground services		Ensure underground services have been identified and marked accurately for depth and position:		
			- Contact Dial before you dig		
			- Use accredited cable locator contractor to test the area		
			 Contact relevant authorities/companies for 'as constructed' plans if necessary 		
			 Hand excavate using a shovel to locate services and mark out prior to any trenching or battering works 		
			Use "Pot holing" techniques if required:		
			- Use extreme care when working near gas mains		
			 When using hand prodders to locate pipes do not use hammers or other implements 		
			Mark all exposed services with flags or devices that can be readily seen		
			Ensure all marked services continue to be visible for the duration of the work.		
	Slips, trips and falls		Be aware of ground condition including changes in level		
			Wear appropriate thick soled covered footwear - NEVER wear thongs or similar footwear		



Јов Ѕ тер	POTENTIAL HAZARD/S	IR	CONTROL MEASURES TO REDUCE RISK	RR	Responsible Person
			INHERENT RISK-RATING (IR) RESIDUAL RISK-RATING (RR)		
			Use high visibility string lines (to avoid tripping hazards)		
			Do not climb or jump over loose building material		
			Do not jump from elevated edges >180mm (concrete slabs etc.)- step carefully and or use prepared access area.		
			Obey any barriers & signage - Be aware of excavations		
			Follow clearly defined detours for pedestrians around hazards		
	Environmental		Do not walk near top edge of excavations; maintain safe distance from edges, voids & pits.		
			NOTE : Some traffic management plans may say that pedestrians have right-of-way. Never assume this. Make visual and verbal contact with plant operator as required.		
			Working outdoors. Ensure:		
	conditions		- Suitable protective clothing		
			- Sun brim on hard hat		
			- Safety glasses - UV Rated		
			- Use 30+ sunscreen		
			- Adequate drinking water		
			- Access to shade during breaks		
			- Adequate breaks		
			 Check weather conditions – do not work in extreme weather – If temperatures extreme (very hot or very cold) undertake risk assessment and establish protocols e.g. frequent rest periods 		
			- Ensure sufficient lighting and visibility.		
	Cuts, abrasions		Wear gloves when handling sharp tools, rocks and other materials.		
	Hearing loss/damage		Wear hearing protection, ensure it is:		



JOB STEP	POTENTIAL HAZARD/S	IR	CONTROL MEASURES TO REDUCE RISK	RR	RESPONSIBLE PERSON
			INHERENT RISK-RATING (IR) RESIDUAL RISK-RATING (RR) - Worn by all persons throughout the period of exposure to noise		
			- Suitable for the type of working environment and the work tasks		
			- Comfortable and correctly fitting for the worker		
			 Regularly inspected and maintained to ensure it remains in good, clean condition. 		
5. Temporary Traffic Control (TMP)	Hit by mobile plant/vehicle		Where temporary road traffic control is required (e.g. kerbside works, materials delivery or pedestrian management):		
			 Approvals and permits are sought from local council and/or state road transport departments where necessary 		
			 A TMP is developed for the temporary works (this can be a separate plan to the Construction TMP if required) 		
			- Only accredited traffic controllers are to perform traffic control duties		
			 All traffic control measures put in place must be implemented as per Australian Standard 1742.3–2009: Manual of Uniform Traffic Control Devices, Part 3: Traffic Control for Works on Roads AS 1742.3-2009 or other requirements as per permit conditions 		
			Traffic controllers must have the accreditation to perform traffic control duties		
			 Traffic controllers must have sufficient experience to setup and control traffic safely and efficiently. 		
	Public and		Pedestrian Access. Ensure:		
	Pedestrian safety		 If closing/modifying a vehicle lane, parking area or footpath the following factors are considered in developing alternative pedestrian access: 		
			○ Travel speed of road traffic		
			○ Traffic volumes		
			Percentage of heavy vehicles		
			○ The alignment of the road		



Јов Ѕтер	POTENTIAL HAZARD/S	IR	CONTROL MEASURES TO REDUCE RISK	RR	RESPONSIBLE PERSON
		<u>'</u>	INHERENT RISK-RATING (IR) RESIDUAL RISK-RATING (RR)	·	
			 If alternative route is immediately adjacent to the road, concrete or water filled barriers to protect pedestrians from road traffic should be used 		
			 Pedestrians will be directed by defined walking paths clearly marked with using appropriate measures (e.g. barriers, fencing hazard netting) 		
			- Signage must be appropriate and easily seen		
			- Temporary pathways must have no trip hazards and the ground/pavement should be free of holes, dips, mud or debris		
			 Mobility impaired e.g. wheelchair access, pram ramps, handrails must be considered in respect to widths, surface and grade 		
			 Barrier fencing flagging or other acceptable method must be erected to prevent the public from entering hazardous areas of the work site 		
			- Access should be monitored through a single-entry point.		
6. Delivery of	Hit by mobile		Alertness at all times. Listen for:		
materials and equipment	plant/vehicle		- Reversing alarms/beepers		
oquipmont			- Calls from Plant Operators		
			 Safety/warning signs, Spotters, traffic barriers etc. must be obeyed as required 		
			- Work positions should be in clear sight of plant operators		
			- Follow traffic management plan requirements.		
			Reversing trucks, ensure:		
			- Never stand between truck and another structure when vehicle is reversing		
			 Always maintain visual contact with driver's mirrors (Remember: if you can't see the driver – he can't see you!) 		
			- Use a spotter where practicable to direct trucks on site.		
			When unloading ensure:		
			- Within Safe working load (SWL) if using hoisting machinery		



JOB STEP POTENTIAL HAZA	RD/S IR	CONTROL MEASURES TO REDUCE RISK	RR	RESPONSIBLE PERSON
7. Marking All harness, belt, la assemblies including arrest assemblies in be legibly and indemarked or labelled permanently by the manufacturer shown the relevant inform listed on the right harmonic column.	ng fall- must :libly e ving ation	- Suitable ground and sufficient room for operation - Delivery driver and other personnel are removed from area (use physical barriers to maintain exclusion zone) If Driver is unloading — establish and enforce exclusion zone - Persons do not stand on or beside delivery vehicle during unloading - Loads are secure and will not free-fall - Use lifting equipment for larger packs. The device designation, such as 'Pole strap'', 'lanyard assembly', etc., The name, trade name or trademark of the manufacturer, The device's serial number, For fall-arrest harnesses and lanyard assemblies, the maximum free fall allowable, Any instruction necessary for fitting, assembly and putting-on, etc., If applicable, a statement for the specific application of the device, A statement showing the device is designed for use in more than one specific configuration together with the applicable limitations, such as attachment points. The location where the primary load-bearing attachment hardware attaches to the pole strap, restraint line or lanyard assembly, The month and year when the device should be discontinued from service, (Maximum limit is 10 years from the date of manufacture. Use harnesses only for the purpose for which they were designed. If used for any purpose other than their intended function, harnesses may fail to provide necessary level of protection, and/or expose the wearer to risk levels that are unacceptable in the performance of the task being carried out. Safety harnesses above 10 years of age must never be used.	2M	



Ј ОВ S ТЕР	POTENTIAL HAZARD/S	IR	CONTROL MEASURES TO REDUCE RISK	RR	RESPONSIBLE PERSON	
O Increation	Democrathe equipment	211	INHERENT RISK-RATING (IR) RESIDUAL RISK-RATING (RR)	OM		
8. Inspection	Remove the equipment from service, if any of	3H	Equipment age is more than 10 years.	2M		
		the conditions on the	he conditions on the	Labels are found obliterated, illegible, missing or removed.		
	right are detected during inspections.		Evidence is found for charring, stiffness or melting, or there are indications of the device being exposed to extreme heat or cold.			
			It shows damage from exposure to organic solvents, caustics or acids.			
			There is indication of excessive wear on the device, such as frayed or furry.			
		There is indication of excessive pitting corrosion, general corrosion, or a broken, worn, distorted, burred or cracked hardware. Knots have formed in any part of the equipment.	There is indication of excessive pitting corrosion, general corrosion, or any broken, worn, distorted, burred or cracked hardware.			
			Knots have formed in any part of the equipment.			
			The device shows visible damage, loss of resilience, discoloration that raises doubts regarding the ability for withstanding potential overloading and the strength of the equipment.			
			Part of the mechanism is found to be not moving freely.			
			There is a visible reduction in the cross-sectional area of webbing or rope, lose or unravelling of fibres, stitching or strands.			
			Approved cleaning methods are unable to remove the excessive contamination.			
			Do not use out-of-date or faulty equipment.			
9. Use	Persons falling	3H	After inspection, lay out the harness and make sure it is not tangled or crossed.	2M		
			On the attachment point on the rear of the harness, attach the lanyard assembly.			
			Wear on the body as like any other similar garment.			
			Connect all buckles, and make sure the belts are not twisted or crossed.			
			Tighten the belts and make the harness fit firmly on the body, do not over tight.			
			Make sure body movements are still full range, while wearing the harness.			



JOB STEP	POTENTIAL HAZARD/S	IR	CONTROL MEASURES TO REDUCE RISK	RR	RESPONSIBLE PERSON
			INHERENT RISK-RATING (IR) RESIDUAL RISK-RATING (RR)		
			Recheck all buckles and belts. If there is evidence of movement, do not use the harness.		
			Fit harnesses properly for safety in use.		
10. Withdrawal from	Equipment must be	3H	The equipment has been involved in a fall, or	2M	
service	removed from service for any of the events listed		The equipment is more than 10 years old, or		
	on the right.		The equipment is deteriorated, damaged or worn.		
			Never use stressed or out-of-date equipment.		
11. Maintenance		3H	Synthetic textile material may be cleaned with warm water and mild soap	2M	
			Harness material should not be cleaned or washed using either abrasive cleaners, solvents, etc.		
		Inspect all fittings, buckles and belts for evidence of damage, distortion or wear.			
			Unauthorized replacement of parts or repairs must not be allowed.		
			Harnesses must be stored in dry, cool areas, hanging from hooks for avoiding entanglement.		
			Contact supplier or manufacturer for any advice on specialist cleaning.		
			Use mild cleaners or soap only.		
			Never use faulty or out-of-date equipment.		
			The device must be returned to supplier or manufacturer for repair, or discard.		
12. On Completion	Slips, trips, falls causing injury		Clean up tools and any waste, and make sure the site is clean and tidy condition		
			Store materials to minimise manual tasks hazards, trip hazards, and the potential for falling objects.		
	Mobile plant		If mobile plant is to be left onsite make sure:		
			- It is left/parked in a secure and safe manner		
			- All keys are removed		



JOB STEP	POTENTIAL HAZARD/S	IR	CONTROL MEASURES TO REDUCE RISK	RR	RESPONSIBLE PERSON
		'	INHERENT RISK-RATING (IR) RESIDUAL RISK-RATING (RR)		
			- It is locked to prevent unauthorised use.		
	Cuts, laceration, puncture wounds		Always wear gloves to avoid sharp edges		
			Never use bare hands to clean equipment (use clean water and stiff brush or other appropriate method).		
	Contact with electricity		Disconnect power tool/extension leads from power point before winding up to prevent a shock if the lead is damaged		
			Inspect leads and power equipment for damage		
	Muscular stress / musculoskeletal disorder (MSD		If safe to do so, remove isolation locks/tags and test appliance for function.		
			Where manual loading/unloading and storage is necessary:		
			- Make sure the access route is clear of hazards		
			- Use hand trucks (trolley) to move heavy materials, where practicable		
			- Use team-lifts where possible.		
	Public safety		If acceptable, remove or add barricades as necessary, contact supervisor and notify job completion.		



EMERGENCY RESPONSE - CALL 000 IMMEDIATELY.

If work is to be conducted on a construction site (or a site controlled by another Employer / PCBU) follow the site-specific Emergency Management Plan. Ensure:

- · Adequate numbers of first aid trained staff are on site when working at heights occurs
- First aiders are trained and competent in managing injuries associated with demolition until emergency services arrive
- All rescue equipment is in good condition, available for use and in close proximity to the work

Ensure workers have access to:

- First aid kit/supplies
- First Aid trained personnel familiar with Resuscitation and emergency response for electric shock
- M/SDS
- Communication devices (check mobile phones will have service in area)

site.	Suitable fire protection equipment.				
	SAFE WORK METHOD STATEMENT (SWMS) PAR	кт 2			
FORMAL TRAINING, LICENCES REQUIRED FOR WORKERS UNDERTAKING THIS TASK:	Relevant Legislation & Codes of Practice □ Retain only the legislation references applicable to your state of operation for this SWMS.				
Delete or add as relevant Licence to Perform High Risk Work (operating certain plant, equipment) TAFE or other recognised training organisation Construction Induction Card (or equivalent) Competent in operation of make/model of plant Emergency procedures – emergency response PPE Traffic Management Plans	Commonwealth, NSW, QLD, ACT Work Health and Safety Act 2011 Work Health and Safety Regulations 2011 Northern Territory Work Health and Safety (National Uniform Legislation) Act 2011 Work Health and Safety (National Uniform Legislation) Regulations SA, Tasmania Work Health and Safety Act 2012 Work Health and Safety Regulations 2012	Victoria: Occupational Health & Safety Act 2004 Occupational Health & Safety Regulations 2007 Compliance Codes: WorkSafe Victoria (2008): Compliance Code: Communicating OHS Across Languages First Aid in the Workplace Prevention of Falls in General Construction Workplace Amenities and Work Environment Codes of Practice: WorkSafe Victoria (1990): No. 13: Building and Construction Workplaces (2000): No. 25: Manual Handling (1995): No. 19: Plant (1998): No. 23: Plant (Amendment No. 1) (2004): No. 29: Prevention of Falls in Housing Construction (2000): No. 24: Hazardous Substances Western Australia Occupational Safety & Health Act 1984 Occupational Safety & Health Regulations 1996 Codes of Practice:			
DETAILS OF SUPERVISORY ARRANGEMENTS FOR WORKERS UNDERTAKING THIS TASK: Delete or add as relevant Suitably qualified supervisors for job Direct on-site supervision Remote site – communication systems/ schedule Audits Spot Checks, etc. Reporting systems DETAILS OF: REGULATORY PERMITS/LICENSES ENGINEERING DETAILS/CERTIFICATES/WORKCOVER. APPROVALS: Delete or add as relevant	Codes of Practice: Safe Work Australia (2011): Construction Work First Aid in the Workplace Managing the Risk of Falls at Workplaces Managing Noise and Preventing Hearing Loss in the Workplace How to Manage Work Health and Safety Risks Hazardous Manual Tasks Managing Risks of Hazardous Chemicals Managing Electrical Risks in the Workplace Managing the Work Environment and Facilities WHS Consultation, Cooperation & Coordination (2005) Excavation Work				
Local council permits Authorisation to work Confined Space Permit Building Approvals EPA approvals/permits Certain plant to be registered with State Authority	PLANT/TOOLS/EQUIPMENT LIST FOR THE JOB. (Make & Model)	REFERENCE DOCUMENTS			
Certain plant to be registered with State Authority PPE to comply with relevant Australian Standards					



SAFE WORK METHOD STATEMENT (SWMS) PART 3

This SWMS has been developed in consultation and cooperation with *employee/workers* and relevant *Employer/Persons Conducting Business or Undertaking (PCBU)*. I have read the above SWMS and I understand its contents. I confirm that I have the skills and training, including relevant certification to conduct the task as described. I agree to comply with safety requirements within this SWMS including risk control measures, safe work instructions and Personal Protective Equipment described.

requirements with	III UIIS OVVIVIO IIIC	Juding Hak Cont	ioi ilicasures, sai	C WOIN INSUIGCUC	nis and i cisonal	TTOLCCLIVE	Lquipii	icht acschbea.	•			
OVERALL RISK CONT			□ 1 Low		☐ 2 MODERATE		□ 3 Н і G н			□ 4 Асите		
EMPLOYEE/W	ORKER NAME	Job R	OLE / POSITIO	N	SIGNATURE			DATE	TIME	R/PCBU/ VISOR		
REVIEW: Ensure all controls are reviewed as per the following: If controls fail to reduce risk adequately When changes to the workplace or work activity occur that create new / different risks where controls may no longer be effective New hazards identified After an incident involving work activities relevant to this SWMS During consultation with relevant persons indicate review is needed A Health and Safety Representative (HSR) requests a review in line with the requirements of the legislation.						Co the wil	 MONITOR: To ensure controls are implemented and monitored effectively: Toolbox /pre-work meetings will be undertaken Relevant persons will be consulted on hazards and contents of SWMS, work plans and other applicable information Control measures will be monitored throughout works:					
REVIEW No.	1	2	3	4	5	6		7	8	9	10	
NAME:												
INITIAL:												
DATE:												